Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: Fencing to BBMP Properties (other than Gardens Parks) ward no 7

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
1	KSRB 2-2 : **Earthwork excavation by manual means** for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. (Page No 6, I.No.2.3)								
	For Fencing								
	UAS Layout	1	100.00	0.80	0.60	48.00			
	Jakkur railway parallel rd	1	210.00	0.80	0.60	100.80			
	Kodandarama temple	1	100.00	0.80	0.60	48.00			
	Police station park, repairs	1	50.00	0.80	0.60	24.00			
	Play ground	1	240.00	0.80	0.60	115.20			
		1	158.00	0.80	0.60	75.84			
						411.84	**Cum**	**394.42**	**162437.93**
	Basic Rate Rs.=	299.00							
	Add 6% A.W Rs. =	17.94							
	Sub Total =	316.94							
	8Km Lead, Loading and Unloading =(2*1.28*8)+57	77.48							
	Total Rate Rs. =	394.42							
2	KSRB M300-14. Excavation for roadwork in all types of **soil by mechanical means** including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications. MORTH Specification No.301 (P-143/19.14)								
	For Lowering								
	UAS Layout	1	40.00	20.00	0.30	240.00			
	Jakkur railway parallel rd	1	40.00	30.00	0.30	360.00			
	Kodandarama temple	1	40.00	30.00	0.40	480.00			
	Play ground	1	50.00	20.00	0.40	400.00			
		1	30.00	20.00	0.40	240.00			
						1720.00	**Cum**	**63.94**	**109976.80**
	Basic Rate Rs.=	41.00							
	Add 6% A.W Rs. =	2.46							
	Sub Total =	43.46							
	8Km Lead, Loading and Unloading =(2*1.28*8)	20.48							
	Total Rate Rs. =	63.94							
3	KSRB M2100-10. Providing and laying **Plain cement concrete of mix 1:3:6** with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	For Fencing								
	UAS Layout	1	100.00	0.70	0.15	10.50			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Jakkur railway parallel rd	1	210.00	0.70	0.15	22.05			
	Kodandarama temple	1	100.00	0.70	0.15	10.50			
	Police station park, repairs	1	50.00	0.80	0.15	6.00			
	Play ground	1	240.00	0.70	0.15	25.20			
		1	158.00	0.70	0.15	16.59			
	Gym equipment kerb stone	1	20.00	0.20	0.10	0.40			
	Gym equipment area	1	6.00	4.00	0.15	3.60			
						94.84	**Cum**	**5421.90**	**514213.00**
	Basic Rate Rs.=	5115.00							
	Add 6% A.W Rs. =	306.90							
	Total Rate Rs. =	**5421.90**							
4	KSRB 5.2-3 : Providing and **constructing granite / trap / basalt size stone masonry** in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two. m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (Page No 25., I.No.5.6).								
	For Fencing								
	UAS Layout	1	100.00	0.60	0.40	24.00			
	Jakkur railway parallel rd	1	210.00	0.60	0.40	50.40			
	Kodandarama temple	1	100.00	0.60	0.40	24.00			
	Police station park, repairs	1	50.00	0.60	0.40	12.00			
	Play ground	1	240.00	0.60	0.40	57.60			
		1	158.00	0.60	0.40	37.92			
	Steel step								
	UAS Layout	1	100.00	0.45	0.40	18.00			
	Jakkur railway parallel rd	1	210.00	0.45	0.40	37.80			
	Kodandarama temple	1	100.00	0.45	0.40	18.00			
	Police station park, repairs	1	50.00	0.45	0.40	9.00			
	Play ground	1	240.00	0.45	0.40	43.20			
		1	158.00	0.45	0.40	28.44			
						360.36	**Cum**	**4871.76**	**1755587.43**
	Basic Rate Rs.=	4596.00							
	Add 6% A.W Rs. =	275.76							
	Total Rate Rs. =	**4871.76**							
	KSRB 5.1.5 : Providing and laying in position **plain cement concrete of Mix 1:2:4** with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.553cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)								
	Casing								
	UAS Layout	1	100.00	0.45	0.10	4.50			
	Jakkur railway parallel rd	1	210.00	0.45	0.10	9.45			
	Kodandarama temple	1	100.00	0.45	0.10	4.50			
	Police station park, repairs	1	50.00	0.45	0.10	2.25			
	Play ground	1	240.00	0.60	0.10	14.40			
		1	158.00	0.60	0.10	9.48			
	mass concrete for fixing equipments	10	0.60	0.60	0.40	1.44			
						46.02	**Cum**	**5747.32**	**264491.67**
	Basic Rate Rs.=	5422.00							
	Add 6% A.W Rs. =	325.32							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Total Rate Rs. =	**5747.32**							
6	Providing and fixing pre cast solid **cement concrete kerb stones** made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30)								
	For Pathway								
	Gym equipment area	1	20.00			20.00			
						20.00			
						44.00	**Nos**	**432.48**	**19029.12**
	Basic Rate Rs.=	408.00							
	Add 6% A.W Rs. =	24.48							
	Total Rate Rs. =	**432.48**							
7	Painting two coats after filling the surface with **synthetic enamel paint** in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19)								
	For Pathway								
	Gym equipment area	1	20.00		0.30	6.00			
						6.00	**Sqm**	**84.80**	**508.80**
	Basic Rate Rs.=	80.00							
	Add 6% A.W Rs. =	4.80							
	Total Rate Rs. =	**84.80**							
8	Providing and laying/fixing cement base, precast, pre polished cement concrete, **designer tiles** 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No-112,I No-								
	Gym equipment area	1	6.00	4.00		24.00			
						24.00	**Sqm**	**1305.92**	**31342.08**
	Basic Rate Rs.=	1232.00							
	Add 6% A.W Rs. =	73.92							
	Total Rate Rs. =	**1305.92**							
9	KSRRB M300-53. **Construction of embankment** with approved material Gravel /Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page 147, Item No 19.60)								
	For Lewelling								
	Beside STP	1	30.00	20.00	0.20	120.00			
	Behind Impact College	1	75.00	85.00	0.20	1275.00			
	BWSSB Overhead Tank	1	40.00	15.00	0.20	120.00			
	Gym equipment area	1	6.00	4.00	0.30	7.20			
	Play ground	1	50.00	20.00	0.20	200.00			
		1	30.00	20.00	0.20	120.00			
						1842.20	**Cum**	**344.50**	**634637.90**
	Basic Rate Rs.=	325.00							
	Add 6% A.W Rs. =	19.50							
	Total Rate Rs. =	344.50							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
10	Supplying and fixing **M.S. Rectangular poles** made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1 :2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 ems. including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) (P.No-266,I No-37.2)								
	Fencing								
	UAS Layout	50	2.50			125.00			
	Jakkur railway parallel rd	105	2.50			262.50			
	Kodandarama temple	505	2.50			1262.50			
	Play ground rising	45	1.40			63.00			
	Police station park, repairs	40	2.10			84.00			
	Play ground	120	2.20			264.00			
		79	2.20			173.80			
						2234.80	**m**	**910.54**	**2034874.79**
	Basic Rate Rs.=	859.00							
	Add 6% A.W Rs. =	51.54							
	Total Rate Rs. =	**910.54**							
11	**Providing chain link fencing 50mm size** of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (P.No-266,I No-37.3)								
	Fencing								
	UAS Layout	1	30.00		2.10	63.00			
	Jakkur railway parallel rd	1	75.00		2.10	157.50			
	Kodandarama temple	1	40.00		2.10	84.00			
	Play ground rising	1	90.00		1.20	108.00			
	Police station park, repairs	1	80.00		1.80	144.00			
	Play ground	1	240.00		1.80	432.00			
		1	158.00		1.80	284.40			
						1272.90	**Sqm**	**757.90**	**964730.91**
	Basic Rate Rs.=	715.00							
	Add 6% A.W Rs. =	42.90							
	Total Rate Rs. =	**757.90**							
12	**Providing and fixing M.S. Block pipe of 38mm dia**, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint(P.No-266,I No-37.4)								
	Fencing								
	UAS Layout	3	30.00			90.00			
	Jakkur railway parallel rd	3	75.00			225.00			
	Kodandarama temple	3	40.00			120.00			
	Play ground rising	2	90.00			180.00			
	Police station park, repairs	2	80.00			160.00			
	Play ground	3	240.00			720.00			
		3	158.00			474.00			
						1969.00	**m**	**432.48**	**851553.12**

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Basic Rate Rs.=	408.00							
	Add 6% A.W Rs. =	24.48							
	Total Rate Rs. =	**432.48**							
13	Providing and fixing **M.S. Gate** as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification. (P.No-45,I No-7.37)								
	Gate								
	UAS Layout	2	3.00		2.40	14.40			
	Jakkur railway parallel rd	1	3.00		2.40	7.20			
	Kodandarama temple	1	3.00		2.40	7.20			
	Play ground	2	3.00		2.40	14.40			
						43.20	**Sqm**	**3192.72**	**137925.50**
	Basic Rate Rs.=	3012.00							
	Add 6% A.W Rs. =	180.72							
	Total Rate Rs. =	**3192.72**							
14	KSRB 15-18.3 : **Providing and applying enamel metal paint** one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.No-45,I No-15.75)								
	Play ground rising old	1	180.00		2.00	360.00			
	Play ground paint	1	180.00		1.80	324.00			
						684.00	**Sqm**	**64.66**	**44227.44**
	Basic Rate Rs.=	61.00							
	Add 6% A.W Rs. =	3.66							
	Total Rate Rs. =	**64.66**							
15	**Supply & fixing of Arm & Pedal Bike :** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 830 MM x 500MM x 1450 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
		1				1.00			
						1.00	**Each**	**212500.0**	**212500.00**
	Data Rate	212500.00							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
16	**Supply & fixing of Elliptical Cross Trainer:** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 845 MM x 865 MM x 1710 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
		1				1.00			
						1.00	**Each**	**175000.0**	**175000.00**
	Data Rate	175000.00							
17	**Supply & fixing of Pull Down Challenger :** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 2570 MM x 840 MM x 2200 MM . Capacity 2 persons. Inclusive of All Taxes and Transportation Charges(Data approved rate)								
		1				1.00			
						1.00	**Each**	**296000.0**	**296000.00**
	Data Rate	296000.00							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
18	**Supply & fixing of Seated Chest Press :** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 1955 MM x 730 MM x 1955 MM . Capacity 2 persons. Inclusive of All Taxes and Transportation Charges(Data approved rate)								
		1				1.00			
						1.00	**Each**	**287500.0**	**287500.00**
	Data Rate	287500.00							
19	**Supply & fixing of Self Weighted Rower :** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. The seat and backrest is made from Rotomoulded LLDPE. Bearings : Maintenance-free ball bearings. Equipment which have sway and moving parts, must have built in limitors that prevent unwanted and ecesssive movement, which can cause injuries. The limitors must be in accordance with EN16630 safety norms. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 1390 MM x 805 MM x 1198 MM . Capacity 1 person. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
		1				1.00			
						1.00	**Each**	**206250.0**	**206250.00**
	Data Rate	206250.00							

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
20	**Supply & fixing of HD Double Health Walker :** All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Footplates made of alloys of Nylon having good thermal stability. Internal Limited means no bump stops or crush points. Bearings : Maintenance-free ball bearings. Scope of delivery : 1 completely pre-assembled equipment modules. Maintenance : Maintain according to EN16630 and the maintenance guide. Size (L*W * H) 2015 MM x 615 MM x 1360 MM . Capacity 2 persons. Inclusive of All Taxes and Transportation Charges (Data approved rate)								
		1				1.00			
	Data Rate	296000.00				1.00	Each	296000.0	296000.00
								Total Construction Cost	**8998786.49**
								12% GST Charges	**903064.38**
								PMC Charges	**98,000.00**
								Sub Total	**9999850.87**
								Utility Shifting, Miscellaneous, Rounding off	**149.13**
								GRAND TOTAL	**10000000.00**

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle 2018-19

4) APPROVED DATA RATE TO BE ENCLOSED

Assistant Engineer
Yelahanka Project Division
BBMP Bangalore

Asst. Executive Engineer,
Yelahanka Project Division
BBMP Bangalore

Executive Engineer,
Yelahanka Project Division
BBMP Bangalore

22/4/2020

Administrative Approval

Accorded For Rs.100.00 Lakhs
Head of A/C...P-0607
CER NO :.....06..... Dt:01/06/2020

E.E. (Project) 1/6

Technical Sanction

Accorded ...Rs.100.00 Lakhs only
Head of A/C..P.0.607
CER NO :.....19..... Dt:01.06.2020

[JA] CE (YNK)